PLANNED VALUE (PV)

_	Week 1	Week 2	Week 3	Week 4	Week 5	Week 6	Week 7	Week 8	Week 9	Week 10	Totals
Work Package A	\$25	\$12	\$8								\$45
Work Package B		\$12	\$15	\$16	\$20	\$15	\$10				\$88
Work Package C					\$15	\$12	\$13	\$8			\$48
Work Package D								\$12	\$12	\$25	\$49
Total for Week, or Planned Value (PV)	\$25	\$24	\$23	\$16	\$35	\$27	\$23	\$20	\$12	\$25	\$230 = BAC

CUMULATIVE % of PLANNED WORK COMPLETE

	Week 1	Week 2	Week 3	Week 4	Week 5	Week 6	Week 7	Week 8	Week 9	Week 10
Work Package A Hours Worked	245	535	300							
Work Package B Hours Worked		50	65	225	475	200	225			
Work Package C Hours Worked					150	160	600	110		
Work Package D Hours Worked								110	120	480
Total Hours Worked for Week	245	585	365	225	625	360	825	220	120	480
Cumulative Total Hours Worked for Week	245	830	1195	1420	2045	2405	3230	3450	3570	4050
Cumulative Percent of Planned Work Completed	6%	20.5%	29.5%	35%	50%	59%	79.8%	85%	88%	100%